

# ESTIMATE

I SLANG ROCK!  
Alberta  
Canada

BILL TO  
**Shawn Kinley**  
Shawn Kinley  
3 Thornlee Crescent Northwest  
Calgary, Alberta T2K 2W1  
Canada  
  
4032289442  
home@shawnkiny.com

**Estimate Number:** 44  
**Estimate Date:** September 11, 2025  
**Valid Until:** October 11, 2025  
**Grand Total (CAD):** \$2,310.00

| Items   | Quantity | Price      | Amount     |
|---|----------|------------|------------|
| <b>Bobcat services</b><br>Bobcat services to auger out holes for metal posts.<br>Min callout \$300 - incl 1st hour on site. Additional<br>hours \$100/hr  | 1        | \$300.00   | \$300.00   |
| <b>Labor</b><br>2 Men to collect material, take to site, set posts and<br>gates at top of property and access to back yard,<br>between home and garage.<br>Posts to be set at 36" depth.<br>Warranty on fence installation 10 years.  | 1        | \$700.00   | \$700.00   |
| <b>Material for Chain Link Fence</b><br>Fence materials, to include all mesh, latches, end<br>posts, hinges, latches, tension bands and 2 x man<br>gates at 36" wide by 5ft high. One gate situated at<br>the top of the property, above the stairs, the other<br>between the home and garage, to access the back<br>yard.<br>Roughly 58 feet of chain link fencing.<br>Customer will provide existing posts. | 1        | \$1,200.00 | \$1,200.00 |

|                           |                   |
|---------------------------|-------------------|
| <b>Subtotal:</b>          | \$2,200.00        |
| gst 5%:                   | \$110.00          |
| <b>Grand Total (CAD):</b> | <b>\$2,310.00</b> |

# ESTIMATE

I SLANG ROCK!

Alberta  
Canada

## Notes / Terms

Following inspection on Tuesday, September 9th 2025, we found the site to have existing post holes, though these were set unevenly and at a depth of around 12" and with tree roots growing into the area. Mr Kinley advised that there was a previous attempts at setting posts, and showed the posts retrieved. No other material was available. In order to correctly set posts, it is recommended that this be at a depth of 36", ensuring that they are set beneath the frost line and with sufficient depth support the weight carried. It is our opinion that the existing holes require drilling to the correct depth before we could proceed to a proper installation of 5ft chain link fencing and gates. It is noted that the customer has started to make some of these holes deeper, but due to tree roots this is difficult.

ISR Contracting would be happy to undertake the project. A date for installation between September 17th to 19th is offered, with the work expected to take a day, with a maximum of 2 days on site.

Payment terms are as follows:

Upon confirmation to proceed, the cost of materials is to be e-transferred to [helenhughes@yahoo.com](mailto:helenhughes@yahoo.com) - materials will be ordered and install date confirmed.

Upon completion of the work, the balance is due immediately. E-transfer is preferred.

In the event that credit card payment is required a 3-4% charge will apply.